


Bledsoe Tapp & Riggert, Inc.

-Quality Land Surveying and Civil Engineering Services-

BEN E. BLEDSOE, L.S.
PHILIP O. TAPP, L.S.
WILLIAM S. RIGGERT, P.E.


359 Landmark Avenue
Bloomington, IN 47404
(812) 336-8277
(812) 384-1114
FAX: (812) 336-0817

PART OF THE SOUTH HALF OF SECTION 17 T7N R1W MONROE COUNTY, INDIANA JOB #989



CICr_111


P.O.C. TRACTS 1, 2 & 3
NE COR SW 1/4 (NW COR SE 1/4)
SEC 17, T7N R1W
MONROE COUNTY, IN



NOTE:

- 1.) A PREVIOUS SURVEY BY BLEDSOE TAPP & RIGGERT DATED AUGUST 6, 1997 WAS USED FOR THE BASIS OF EXTERIOR BOUNDARIES OF TRACTS 1-3. THE INTERIOR LINES WERE ESTABLISHED AS REQUIRED BY THE CLIENT.
- 2.) THE SUBJECT DEEDS ARE IN THE NAME OF JEFFREY & LOUAN RAY DR. 477, PG. 76 & CEDAR GLEN LLC DR. 464, PG. 332 & DR. 464 PG. 329. THE PROPERTY IS CURRENTLY TAXED AS FIVE SEPARATE PARCELS.

See 17



LEGAL DESCRIPTION:

A part of the Southeast quarter of Section 17, Township 7 North, Range 1 West, bounded and described as follows:

Beginning at a point that is 1852.5 feet North and 1620.0 feet West of the Southeast corner of the said Southeast quarter and on the East Right of Way line of State Road # 37; thence running Northeasterly over and along said East Right of Way line of said State Road # 37 for a distance of 236.0 feet; thence running East for a distance of 1150.0 feet; thence running South for a distance of 719.0 feet; thence running West for a distance of 377.0 feet; thence running North for a distance of 283.0 feet; thence running West for a distance of 483.0 feet; thence running North for a distance of 200.0 feet; thence running West for a distance of 316.0 feet and to the East Right of Way line of State Road # 37.

A part of the Southeast quarter of Section 17, Township 7 North, Range 1 West, bounded and described as follows:

CHARTER LINE OF SURVEY:

A circular seal for James S. Strong, a Registered Land Surveyor in the State of Indiana. The seal features the name "JAMES S. STRONG" in an arc at the top, "REGISTERED" in an arc below it, the number "No. 9234" in the center, "STATE OF INDIANA" in an arc below the number, and "LAND SURVEYOR" in an arc at the bottom. The seal is surrounded by a decorative border of small dots.

James S. Strong, L.S. 20234

TRI CO SURVEYING & MAPPING


Edmund O. Farkas
Registered Land Surveyor

(812) 876-2305

P. O. Box 96
Ellettsville, Indiana 47429

RSID000688

See 17
Sanders, Noble to
Lee, Richard
Sec 17. Clear Cr.



SCALE: 1" = 30'

CLCr_I11

I, Edmund O. Farkas hereby certify that I am a Registered Land Surveyor; licensed in compliance with the Laws of the State of Indiana; that the above plat and enclosed description correctly represent a survey completed by me on June 2, 1976; that all monuments shown thereon actually exist, and that their location and type to the best of my knowledge are accurately shown, and also certify that all improvement on said surveyed property do not encroach upon adjacent properties, nor are there any encroachments upon said surveyed property by adjacent properties.

Edmund O. Farkas
Registered Land Surveyor
In. Reg. No. S0114



REAL ESTATE TRANSFER

JUN 17 1976

John W. Davis
Auditor Monroe County, Ind.

TRI CO SURVEYING & MAPPING

Edmund O. Farkas
Registered Land Surveyor

(812) 876-2305

P. O. Box 96
Ellettsville, Indiana 47429


Description:

A part of the North Half of the Southeast Quarter of Section Seventeen (17), Township Seven (7) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows:

Beginning 557.15 feet South and 1459.48 feet West from the Northeast Corner of said Quarter Section, thence North Eighty-Eight (88) Degrees and Fifty-Two (52) Minutes East on an Existing fence line 142.00 feet, thence North One (01) Degrees and Eighteen (18) Minutes West 105.00 feet to a pipe, thence North Eighty-Seven (87) Degrees and Six (06) Minutes West 142.51 feet to an iron pipe, thence South One (01) Degrees and Twenty-Two (22) Minutes East 115.00 feet to the place of beginning.

Containing 0.36 Acres, more or less.

Also a strip of land being Eight (8) feet in width and located along the South Line of a black top driveway leading from the Northwest Corner of the above described property to State Road No. 37, and running to a Northwesterly direction from the said Northwest Corner, the said strip of land only for driveway purposes and the right to use said Eight (8) foot strip for ingress and egress.


Edmund O. Farkas R.L.S.

PLAT OF LEGAL SURVEY MADE AT REQUEST OF WANDA MOORE.

LOCATED IN THE S.W. 1/4 OF THE N.E. 1/4 OF SEC. 17, T7N-R1W.

Surveyed by Nelson L. Prall - June 22, 1976.

Assistants: A.W. Girdley.



P.G. McWilliams.

M.D. Mundy.

Drawn by Hugh Buercklin

Entered in Legal Survey Book _____ on Page _____
on the _____ day of _____ 1976.

Delivered to the Monroe County Surveyor on 7- -76.
Nelson L. Prall.



Scale: 1" = 40' except as noted N.T.S.

LEGEND:

⊗ = 1/2" Iron Pipe with Yellow Plug
marked Prall-10234.

⊗ R.R. = Railroad Spike.

- = Fence.


● = Nail.

N.T.S. = Not to Scale.


(Sandra A. Eads
Book 169 Page 520)

(Wanda Moore
Book 241 Page 126)
0.35 Acre.

SEE EXHIBIT "A".
For References.



RS 17C00689



RSID000629

NELSON L. PRALL, P. E. & L. S.

- ATTORNEY AT LAW -

CIVIL ENGINEERING AND LAND SURVEYOR

Indiana Professional Engineers License No. 2559

Indiana Professional Land Surveyor License No. 10,234

May 17, 1976

FROM: Nelson L. Prall, Land Surveyor

TO: Wanda Moore
Saundra A. Eads
Larry D. and Bette J. Clark

This is to notify you that at the request of Wanda Moore that sometime on or after Tuesday, June 8, 1976 I will proceed to locate the lines between your properties. This survey shall be made in accordance with the Indiana Code of 1971, title 17, article 3 chapter 63.

This Act also states that the survey can be started earlier if all the owners shall consent in writing to an earlier starting date. Therefore, if all property owners listed above consent in writing to an earlier starting date, I can start it earlier.

After the survey is completed and has been recorded in the Legal Survey Record Book, any property owner involved has 90 days in which to file an objection to the survey in the Monroe County Circuit Court.

A seceond notice will be sent to each of you within ten days after the filing of said survey.

Yours truly,

Nelson L. Prall

Nelson L. Prall
Land Surveyor

NLP/bp

AS ID000689

NELSON L. PRALL, P. E. & L. S.

- ATTORNEY AT LAW -

CIVIL ENGINEERING AND LAND SURVEYOR

Indiana Professional Engineers License No. 2559

Indiana Professional Land Surveyor License No. 10,234

July 1, 1976

FROM: Nelson L. Prall, Land Surveyor

TO: Wanda Moore
Saundra A. Eads
Larry D. and Bette J. Clark

This is to notify you that the survey made at the request of Wanda Moore has been completed. It was presented to the County Surveyor on July 1, 1976 for entry in his files. He has no legal survey Record Book.

If any property owners object to this survey, they have 90 days from July 1, 1976 in which to file their objections to the survey in Monroe County Circuit Court. If no protest is filed, the lines established by this survey are binding on all property owners involved.


Yours truly,

Nelson L. Prall

Nelson L. Prall
Land Surveyor

Enclosure:

NLP/bp



Plot of Legal Survey made at Request of Wanda Moore RS.D000689.

Suru to NLP G-22-76


Asst: - A. W. Girdley

P.G. McWilliams

M. D. Mundy

Drawn By H B

Entered in Logal Survey Book _____ on P _____ on ^{the} _____ day of _____ 1976



PLAT OF LEGAL SURVEY MADE AT REQUEST OF WANDA MOORE.
LOCATED IN THE SW 1/4 OF THE NE 1/4 OF SEC. 17, T7N-R1W.

Surveyed by Nelson L. Prall - June 22, 1976.



Assistants: A.W. Girdley.

P.G. McWilliams.

M.D. Mundy.

Drawn by Hugh Buercklin

Entered in Legal Survey Book _____ on Page _____
 on the _____ day of _____ 1976.



Scale: 1" = 40' except as noted N.T.S.

LEGEND:

⊗ = 1/2" Iron Pipe with Yellow Plug
 marked Prall-10234.

⊗ R.R. = Railroad Spike.

- = Fence.


● = Nail.

N.T.S. = Not to scale.

(Sandra A. Eads
 Book 169 Page 520)

(Wanda Moore
 Book 241 Page 126)
 0.35 Acre.

SEE EXHIBIT "A".



CEDAR BLUFF ROAD.

Nail Found.
 514.72' N.T.S.

Iron Pipe Found.
 0.24 N.T.S.
 217.98 N.T.S.

461.10' N.T.S.
 136' N.T.S.

CICr_G11

819.60' N.T.S.

1/4 Sec. Line

605 N.T.S.

SW 1/4 of NE 1/4 Sec. 17 T7N-R1W.

(Larry D. & Bette J. Clark
 Book 189 Page 508)


#3

#4

#1

#2

#5



Chew Creek Sec 17

NELSON L. PRALL, P. E. & L. S.

- ATTORNEY AT LAW -

CIVIL ENGINEERING AND LAND SURVEYOR

Indiana Professional Engineers License No. 2559

Indiana Professional Land Surveyor License No. 10,234

May 17, 1976

FROM: Nelson L. Prall, Land Surveyor

TO: Wanda Moore
Saundra A. Eads
Larry D. and Bette J. Clark

This is to notify you that at the request of Wanda Moore that sometime on or after Tuesday, June 8, 1976 I will proceed to locate the lines between your properties. This survey shall be made in accordance with the Indiana Code of 1971, title 17, article 3 chapter 63.

This Act also states that the survey can be started earlier if all the owners shall consent in writing to an earlier starting date. Therefore, if all property owners listed above consent in writing to an earlier starting date, I can start it earlier.

After the survey is completed and has been recorded in the Legal Survey Record Book, any property owner involved has 90 days in which to file an objection to the survey in the Monroe County Circuit Court.

A seceond notice will be sent to each of you within ten days after the filing of said survey.

Yours truly,

Nelson L. Prall

Nelson L. Prall
Land Surveyor

NLP/bp

CC-171

NELSON L. PRALL, P. E. & L. S.

ATTORNEY AT LAW

CIVIL ENGINEERING AND LAND SURVEYOR

Indiana Professional Engineers License No. 2559

Indiana Professional Land Surveyor License No. 10,234

July 1, 1976

FROM: Nelson L. Prall, Land Surveyor

TO: Wanda Moore

Saundra A. Eads

Larry D. and Bette J. Clark

This is to notify you that the survey made at the request of Wanda Moore has been completed. It was presented to the County Surveyor on July 1, 1976 for entry in his files. He has no legal survey Record Book.

If any property owners object to this survey, they have 90 days from July 1, 1976 in which to file their objections to the survey in Monroe County Circuit Court. If no protest is filed, the lines established by this survey are binding on all property owners involved.

Yours truly,

Nelson L. Prall

Nelson L. Prall
Land Surveyor

Enclosure:

NLP/bp

RS10000689

990±

216-70

11-4-72

Very Bad.

Except what has been sold

Robert May

Wanda Moores Tract was

Sold to May which is the

Reason for D.R. 219 P. 339

The 819.6' will hold & Moores will
get the rest to S.R. 37 unless the
highway R/W is less than 990'

237-72
Kenneth Coleman
and R/W
Bad Deed

SR 37

350'

630
228' N &
622' E

N 05° 30' W
185'

120'

Red Deed
165-352
6-21-65

Again
189-191
4-10-69

214

214

250' W of
989.45 E &
209.51 N
100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

120'

60'

170-171
2-18-66

60

214

250'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

120'

60'

146-1
9-17-62

60

214

250'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

120'

60'

190

60

214

250'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

120'

60'

190

60

214

250'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

120'

60'

190

60

214

250'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

120'

60'

190

60

214

250'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

120'

60'

190

60

214

250'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

120'

60'

190

60

214

250'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

120'

60'

190

60

214

250'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

120'

60'

190

60

214

250'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

100'

Harry
Barker
183-161
4-5-68

SW cor
SW
NE
Sec. 17
7N
1W

105-269
4-10-65

101'

101'

101'

101'

101'

101'

101'

Eva Fox

101'

101'

101'

101'

101'

101'

101'

148-6
11-26-62

101'

101'

101'

101'

101'

101'

101'

233-214
Keith
Smith
4-3-75

101'

101'

101'

101'

101'

101'

101'

173-83
Kenneth
Willis
8-2-66

101'

101'

101'

101'

101'

101'

101'

121-554
Fred
Browning

101'

101'

101'

101'

101'

101'

101'

163-385
Donald
Lowery
3-3-65

101'

101'

101'

101'

101'

101'

101'

189-274
4-21-69

101'

101'

101'

101'

101'

101'

101'

140-447
10-13-61

101'

101'

101'

101'

101'

101'

101'

189-508
Larry
Clark
5-10-69

101'

101'

101'

101'

101'

101'

101'

1704-10
219-339
for this

101'

101'

101'

101'

101'

101'

101'

140-447
10-13-61

101'

101'

101'

101'

101'

101'

101'

189-508
Larry
Clark
5-10-69

101'

101'

101'

101'

101'

101'

101'

140-447
10-13-61

101'

101'

101'

101'

101'

101'

101'

189-508
Larry
Clark
5-10-69

101'

101'

101'

101'

101'

101'

101'

140-447
10-13-61

101'

101'

101'

101'

101'



FILED
MAY 21 1987
Rodney J. Brown
Auditor Monroe County, Indiana

COMBINED DESCRIPTION: Heltenburg Property

A part of the Southwest quarter of the Southeast quarter and a part of the Northwest quarter of the Southeast quarter of Section 17, Township 7 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at a point 652.00 feet North of the Southwest corner of the said Southwest quarter of the Southeast quarter, thence running East for 493.00 feet, thence running North 02 degrees 24 minutes 27 seconds East for 440.39 feet, thence running East for 472.50 feet and to the centerline of Old State Road #37, thence running with the said road centerline North for 304.00 feet, thence leaving the said road centerline and running West for 1006.50 feet and to the West line of the said Southeast quarter of said Section 17, thence running South on the said West line for 731.50 feet and to the point of beginning. Containing in all 13.24 acres, more or less.

Raymond Graham


RAYMOND GRAHAM
R.P.E. 8409 L.S. 9978 IND
3215 N Smith Pike
Bloomington, Indiana
March 3, 1987



(812) 334-8941

REDAUCED

Countdown



SCALE
1"=100'


DESCRIPTION:

A part of the Southeast quarter of Section 17, Township 7 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at a point 533.25 feet South of the Northwest corner of the said Southeast quarter and on the West line of said quarter; thence running South 88 degrees 43 minutes 55 seconds East for 285.16 feet and to a point that is 85.00 feet Westerly from the Northwest corner of Lot Number 7 in Robert Johnson Addition; thence running parallel with the West line of the said Lot number 7 South 01 degree 36 minutes 45 seconds West for 170.00 feet and to a point that is 85.00 feet Westerly from the Southwest corner of the said Lot 7 in said Addition; thence running North 88 degrees 43 minutes 29 seconds West for 280.38 feet and to the said West line of the said Southeast quarter section; thence North over and along the said West line of the said Southeast quarter for 170.00 feet and to the point of beginning. Containing 1.10 acres, more or less.

ALSO, Lot Number 7 and the West half of Lot Number 6 in Robert Johnson Addition, which is located in the Southeast quarter of Section 17, Township 7 North, Range 1 West.

ALSO, the following described real estate in Section 17, Township 7 North, Range 1 West, Monroe County, Indiana, to-wit: beginning at the Northwest corner of Lot Number 7 in Robert Johnson Addition; thence running in a Westerly direction for 85.00 feet; thence running in a Southerly direction for 170.00 feet; thence running in a Easterly direction for 85.00 feet and to the Southwest corner of the said Lot 7; thence running in a Northerly direction over and along the West line of the said Lot 7 for 170.00 feet and to the point of beginning. Containing 0.33 acres, more or less.

Containing in all three above described tracts, 2.02 acres, more or less.



Raymond Graham
RAYMOND GRAHAM
R.P.E.. 8409 L.S. 9978 IND
3215 N. Smith Pike
Bloomington, Indiana
February 16, 1990



Corrected

Sec 17
Clear Creek

CICr_G11

NW CORNER, SE 1/4
S 17, T7N, R1W

525 CROSS ST.



HOUSE DETAIL
SCALE: 1"=30'

SCALE: 1"=100'


DESCRIPTION

A part of the Southeast quarter of Section 17, Township 7 North, Range 1 West, Monroe County, Indiana, described as follows:

Commencing at the Northwest corner of the said Southeast quarter section; thence South along West line of said quarter section 533.25 feet to the point of beginning; thence South 88 degrees 43 minutes 55 seconds East 285.16 feet to a point that is 85.00 feet Westerly from the Northwest corner of Lot Number 7 in Robert Johnson Addition; thence South 88 degrees 35 minutes 35 seconds East for 85.00 feet along the projection of Cross Street in said Addition to the Northwest corner of said Lot Number 7; thence along the North line of said Lot Number 7, South 89 degrees 35 minutes 35 seconds East 100.00 feet and to the Northeast corner of said Lot Number Seven and the Northwest corner of Lot Number 6 in said Addition; thence along the North line of said Lot Number 6 South 89 degrees 35 minutes 35 seconds East for 50.00 feet to the midpoint of the said North line of Lot Number 6; thence South 01 degrees 36 minutes 45 seconds West 170.00 feet, parallel with the West line of said Lot Number 6, to the South line of said Addition; thence North 89 degrees 35 minutes 35 seconds West along said South line 50.00 feet to the Southwest corner of said Lot Number 6; thence continuing along said South line North 89 degrees 35 minutes 35 seconds West 100.00 feet and to the Southwest corner of Lot Number 7 in said Addition; thence continuing along the projection of said South line of said Addition North 89 degrees 35 minutes 35 seconds West for 85.00 feet; thence North 88 degrees 43 minutes 29 seconds West for 280.38 feet and to the West line of said quarter Section; thence along said West line North 170.00 feet and to the point of beginning. Containing in all 2.02 ACRES.

CERTIFICATION:

I hereby certify that the plat shown is a true and complete survey of the described property, and further certify that all improvements are wholly within the boundaries of said described property, and that the said improvements do not encroach upon any other property, nor are there any encroachments from any other property on said surveyed property.



Raymond Graham
Raymond Graham
R.P.E 8409 L.S. 9978 IN
3215 N. Smith Pike
Bloomington, Indiana
February 11, 1994

DESCRIPTION

A part of the Southeast quarter of Section 17, Township 7 North, Range 1 West, Monroe County, Indiana, described as follows:

Commencing at the Northwest corner of the said Southeast quarter section; thence South along West line of said quarter section 533.25 feet to the point of beginning; thence South 88 degrees 43 minutes 55 seconds East 285.16 feet to a point that is 85.00 feet Westerly from the Northwest corner of Lot Number 7 in Robert Johnson Addition; thence South 88 degrees 35 minutes 35 seconds East for 85.00 feet along the projection of Cross Street in said Addition to the Northwest corner of said Lot Number 7; thence along the North line of said Lot Number 7, South 89 degrees 35 minutes 35 seconds East 100.00 feet and to the Northeast corner of said Lot Number Seven and the Northwest corner of Lot Number 6 in said Addition; thence along the North line of said Lot Number 6 South 89 degrees 35 minutes 35 seconds East for 50.00 feet to the midpoint of the said North line of Lot Number 6; thence South 01 degrees 36 minutes 45 seconds West 170.00 feet, parallel with the West line of said Lot Number 6, to the South line of said Addition; thence North 89 degrees 35 minutes 35 seconds West along said South line 50.00 feet to the Southwest corner of said Lot Number 6; thence continuing along said South line North 89 degrees 35 minutes 35 seconds West 100.00 feet and to the Southwest corner of Lot Number 7 in said Addition; thence continuing along the projection of said South line of said Addition North 89 degrees 35 minutes 35 seconds West for 85.00 feet; thence North 88 degrees 43 minutes 29 seconds West for 280.38 feet and to the West line of said quarter Section; thence along said West line North 170.00 feet and to the point of beginning. Containing in all 2.02 acres.




Raymond Graham
Raymond Graham
R.P.E 8409 L.S. 9978 IN
3215 N. Smith Pike
Bloomington, Indiana
February 10, 1994

Sec 17
Clear Creek

Raymond to Secretary 1/2

PLAN OF SURVEY

Noah & Judith Dike




SCALE: 1" = 150'

(R) BASED ON DEED RECORD

(F) BASED ON FIELD MEASUREMENTS
THIS SURVEY

① 5/8" REBAR WITH PLASTIC CAP
SET THIS SURVEY

Kevin B. Potter
Kevin B. Potter, P.E. & L.S.
P.O. Box 5982
Bloomington, Indiana
47407



Sept. 16, 1994

LEGAL DESCRIPTION

The existing legal description for the subject property is recorded in deed record 423, page 81, Office of the Recorder of Monroe County, Indiana, as listed below:

A part of the Southwest Quarter of the Southeast Quarter and a part of the Northwest Quarter of the Southeast Quarter of Section 17, Township 7 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at a point 552.00 feet North of the Southwest corner of the said Southwest Quarter of the Southeast Quarter; thence running East for 493.00 feet; thence running North 02 degrees 24 minutes 27 seconds East for 440.39 feet; thence running East for 472.50 feet and to the centerline of Old State Road #37; thence running with the said road centerline North for 304.00 feet; thence leaving the said road centerline and running West for 1006.50 feet and to the West line of the said Southeast Quarter of said Section 17; thence running South on the said West line for 731.50 feet and to the point of beginning. Containing 13.24 acres, more or less.

Subject to all taxes.

Subject to the Right-of-way of Old State Road #37 along the East side of the subject real estate.

Subject to an Easement to Southern Indiana Power Co., recorded November 2, 1925, at page 276 of Miscellaneous Record 10 in the office of the Recorder of Monroe County, Indiana.

Subject to a Gas Line Easement to Interstate Public Service Co., recorded May 7, 1930, at page 129 of Miscellaneous Record 14; assigned to Indiana Gas & Water Co., Inc., by Assignment recorded September 18, 1945, at pages 499 through 535 of Deed Record 98 in the office of the Recorder of Monroe County, Indiana.

Subject to an Easement to Indiana Bell Telephone Company recorded September 28, 1933, at page 535 of Miscellaneous Record 15 in the office of the Recorder of Monroe County, Indiana.

Subject to an Easement for Gas Lines to Indiana Gas & Water Co., Inc., recorded March 7, 1947, at page 52 of Deed Record 101 in the office of the Recorder of Monroe County, Indiana.

Subject to an Easement for Gas Line to Indiana Gas & Water Co., Inc., recorded March 7, 1947, at page 520 of Deed record 101 in the office of the Recorder of Monroe County, Indiana.

Subject to an Easement for ingress and egress to Earl E. Shields and Thelma F. (Perry) Shields, husband and wife, recorded August 30, 1979, at page 288 of Deed Record 270 in the office of the Recorder of Monroe County, Indiana.

Based on this recent survey, the subject property is found in accordance with the following revised description:


Part of the Southwest quarter of the Southeast quarter of Section 17, Township 7 North, Range 1 West, Clear Creek Township, Monroe County, Indiana, more particularly described as follows:


Commencing at a wood post found at the Southwest corner of said quarter quarter section; thence North 00 degrees 10 minutes 04 seconds East along a fence line 651.29 feet to a rebar with cap set at the point of beginning; thence South 88 degrees 21 minutes 38 seconds East along a fence line 491.90 feet to a rebar with cap; thence North 04 degrees 47 minutes 40 seconds East along a fence line 439.80 feet to a rebar with cap; thence North 89 degrees 30 minutes 13 seconds East 421.72 feet to a rebar with cap set on the West right-of-way of Old State Road No. 37; thence continuing North 89 degrees 30 minutes 13 seconds East 50.02 feet to the centerline of Old State Road No. 37; thence North 01 degrees 05 minutes 00 seconds East along said centerline 254.82 feet; thence South 89 degrees 45 minutes 17 seconds West 50.02 feet to a rebar with cap set on the West right-of-way line of Old State Road No. 37; thence continuing South 89 degrees 45 minutes 17 seconds West along a fence line 953.00 feet to a rebar with cap; thence South 00 degrees 10 minutes 04 seconds West along a fence line 678.76 feet to the point of beginning, containing 10.923 acres, more or less.

Subject to a 50.00 foot right-of-way for Old State Road No. 37 and subject to all other easements and rights-of-way of record.

CERTIFICATION

I, Kevin B. Potter, Indiana L.S. S 0487, hereby certify that the attached plat and legal description represents a Class "C" survey performed in accordance with survey standards as set forth in Title 864, chapter 12 of the Indiana Administrative Code, and in witness thereof I hereunto attach my hand and seal this 16th day of September, 1994.


Kevin B. Potter, L.S. S 0487
P.O. Box 5982
Bloomington, Indiana 47407



REPORT of SURVEY
Noah and Judith Dike
Sec. 17, T7N, R1W

In accordance with Title 864, chapter 12 of the Indiana Administrative Code, a report of survey is required to explain procedures used in establishing the subject property lines and to provide an opinion regarding uncertainties in the subject property lines.

The following procedures were used to establish the subject property lines:

1. The wood post found (point 47) was accepted as the Southwest corner of the Southeast quarter of Section 17.
2. The wood post found (point 50) was accepted as being on the West line of the Southeast quarter of Section 17.
3. The South line was accepted on the fence line between fence corner points 45 to 40.
4. The Southwest corner (point 60) was set at the intersection of the lines between points 47 to 50 and 45 to 40. This corner is 1.60 feet East of the existing fence corner.
5. The Southeast corner of the West part (point 66) was set on the line between points 45 to 40 and at the record distance of 227 feet West of the metal "T" post (point 65).
6. The Southeast corner of the East part (point 67) was set at the intersection of the centerline of Old State Road 37 and the line of fence posts along the North side of Beacher.
7. The Northwest corner of Long (point 61) was set at the intersection of the fence posts on the North line of Beacher and the fence on the West line of Norman and Long.
8. The existing fence line was used as the North line of the subject property. An average position of several fence locations were used to obtain the final line since the fence was not exactly straight. Based on the deed record, this fence line is also the approximate North line of the Southwest quarter of the Southeast quarter of Section 17.
9. The Northeast corner of the East part (point 89) was set at the intersection of the North fence line projected East and the centerline of Old State Road 37.
10. The Northwest corner (point 68) was set at the intersection of the North fence line and the line between points 47 to 50. This corner is 0.70 feet North of fence corner point 50.
11. The right-of-way for Old State Road 37 was set 50 feet from the centerline as per the 1927 state highway plans for State Highway No. 37. The record plan bearing of North 01 degrees 05 minutes 00 seconds East was used as the basis of bearings for this survey.

Uncertainties in the final boundary positions can result from any or all of the following factors:

- A. Availability and Condition of Reference Monuments
(point 47) - Wood corner post accepted as the Southwest corner of the Southeast quarter of Section 17.

(point 28 and 104) - Iron pipe and rebar found on the right-of-way line on the East side of the Michael East property.

(points 13 and 30) - State highway concrete right-of-way markers found on the West right-of-way line.

No monuments were referenced in the subject and adjoining legal descriptions.

B. Ambiguities in Recorded Legal Descriptions

1. Prior to May 20, 1987, the subject parcel was recorded in deed record 336, page 18, as three separate tracts plus one exception. One of these tracts was a 3 rod by 61 rod (49.5 feet by 1006.5 feet) tract located North of our staked North line between points 68 to 89. The record lists this tract as 1.50 acres with the calculated acreage equal to 1.144 acres.

This tract is entirely overlapped by the Bainbridge adjoining property to the North which has the fence line between points 68 to 89 as a record South line. Even though record title search finds a good chain of title for this tract belonging with the subject property, this area is fenced and occupied by Bainbridge. The 1927 State Highway plans for State Road No. 37 also shows the fence line as being a property line.

2. The exception listed in deed record 336, page 18 is listed as being 0.86 acres and is currently split into two tracts owned by Robert Long and Roy Norman.

3. The first tract listed in deed record 336, page 18 is 11.50 acres. The third tract is 1.10 acres but is located entirely within the 11.50 acre tract. The actual area of tract three based on the record dimensions is 1.67 acres instead of 1.10 acres.

4. On February 20, 1987, a plat of survey of the subject property was prepared by Raymond Graham, L.S. No. 9978. Graham also redefined the subject property into one legal description as recorded in deed record 336, page 19. This description is also the current record description used in deed record 423, page 81.

A surveyor's affidavit prepared by attorney Morris H. Erickson and signed by Graham was prepared on March 4, 1987 and recorded in Deed Record 336, page 17. This document states that the Graham combined description as recorded in Deed Record 336, page 19 is the same real estate as described in deed record 336, page 18 which contains the three tracts plus the exception.

5. Review of the combined Graham description finds that the 1.50 acre tract North of the fence was included in the combined description even though it has been occupied by the adjoining owner since 1927 or before and is also included within the adjoiner's legal description.

The combined area in the Graham description exactly conforms with the area obtained by adding the record areas of the three tracts and subtracting the exception area. This creates errors since the entire area of tract three is entirely within the described area for tract one and the actual tract two area based on record dimensions is 1.144 acres instead of the record 1.50 acres.

6. The Graham survey also shows no lines of occupation, no monuments set or found, and no overlap with the North adjoiner.

7. The current record description as recorded in Deed Record 423, page 81 lists the starting call as being "552.00 feet North of the Southwest corner of the Southwest quarter of the Southeast quarter". The field distance and the Graham description in Deed Record 336, page 19 has the starting call as 652.00 feet North instead of 552.00 feet North.

8. The acreage of the subject parcel based on the current survey is 10.923 acres which is 2.317 acres less than the record 13.24 acres.

C. Inconsistencies in Lines of Occupation

1. The record North line of the subject parcel is 49.5 feet North of the fence line between points 68 to 31. Bainbridge is occupying and maintaining this 49.5 foot strip.

2. The Southwest corner (point 60) is 1.60 feet East of the fence corner (point 45).

3. All other monumented lines are within 1 foot or less from the existing fence lines.

D. Theoretical Uncertainty

Due to random errors caused by survey instrument precision and survey field methods used, the theoretical uncertainty of all points in this survey is 0.30 feet which meets the requirements of a Class "C" survey as defined in the survey standards. This means that the actual field location of all points in this survey is within this uncertain distance from the point locations based on the survey plat bearings and distances.



Kevin B. Potter, L.S. S 0487
P.O. Box 5982
Bloomington, Indiana 47407

Robert C. Sipes, Registered Land Surveyor

Ind. Reg. No. 9016

P.O. Box 5311


Phone (812) 333-2984

Bloomington, IN 47407

PLAT OF SURVEY

October 11, 1994


Part of SW 1/4 of SE 1/4 of Section 17, 7N-1W, Monroe County, IN



Signed:

Robert C. Sipes

Surveyors Job No. 94101101



Robert C. Sipes, Registered Land Surveyor

Ind. Reg. No. 9016
P.O. Box 5311

Phone (812) 333-2984
Bloomington, IN 47407

SURVEYOR LOCATION REPORT

THIS REPORT IS BASED ON LIMITED ACCURACY DATA AND THEREFORE NO DATA HEREIN SHOULD BE USED FOR CONSTRUCTION OR ESTABLISHING BOUNDARY OR FENCE LINES.

PROPERTY ADDRESS: 8450 South Old State Road #37
PROPERTY DESCRIPTION:

Dike, Judith

Part of the Southwest quarter of the Southeast quarter of Section 17, Township 7 North, Range 1 West, Clear Creek Township, Monroe County, Indiana, more particularly described as follows:

Commencing at a wood post found at the Southwest corner of said quarter quarter section; thence North 00 degrees 10 minutes 04 seconds East along a fence line 651.29 feet to a rebar with cap set at the point of beginning; thence South 88 degrees 21 minutes 38 seconds East along a fence line 491.90 feet to a rebar with cap; thence North 04 degrees 47 minutes 40 seconds East along a fence line 439.80 feet to a rebar with cap; thence North 89 degrees 30 minutes 13 seconds East 421.72 feet to a rebar with cap set on the West right-of-way of Old State Road No. 37; thence continuing North 89 degrees 30 minutes 13 seconds East 50.02 feet to the centerline of Old State Road No. 37; thence North 01 degrees 05 minutes 00 seconds East along said centerline 254.82 feet; thence South 89 degrees 45 minutes 17 seconds West 50.02 feet to a rebar with cap set on the West right-of-way line of Old State Road No. 37; thence continuing South 89 degrees 45 minutes 17 seconds West along a fence line 953.00 feet to a rebar with cap; thence South 00 degrees 10 minutes 04 seconds West along a fence line 678.76 feet to the point of beginning, containing 10.923 acres, more or less.

Subject to a 50.00 foot right-of-way for Old State Road No. 37 and subject to all other easements and rights-of-way of record.

Subject Property is not located within a designated flood plain.

DESIGNATED PARTIES

MORTGAGEE
OR ASSIGNEES:
TITLE CO.:
OTHER:

REFERENCE NO.

REFERENCE NO.

I, the undersigned, an Indiana Registered Land Surveyor, hereby certify that on the date shown, I supervised the inspection of the real estate described herein at the Address indicated. THIS LOCATION REPORT WAS PREPARED FOR USE BY THE DESIGNATED PARTIES ONLY AND FOR NO ONE ELSE. THE ACCURACY OF THE LOCATION DATA SHOWN IS LIMITED TO THAT REQUIRED BY THE INDIANA "SURVEYOR LOCATION REPORT" MINIMUM REQUIREMENTS UNLESS OTHERWISE SPECIFIED AND EXPLAINED ON THIS DOCUMENT. IF A MORE ACCURATE OR DETAILED LAND SURVEY IS DESIRED OR IF CORNER MONUMENTS ARE REQUIRED, AN INDIANA LAND TITLE SURVEY SHOULD BE ORDERED.

I further certify that to the best of my knowledge this Location Report conforms with the SURVEYOR LOCATION REPORT Minimum Requirements, as adopted by the Indiana Society of Professional Land Surveyors, Inc., on January 29, 1981, and approved by the Title Underwriters of Indiana, Inc., on March 1986.


CERTIFICATION DATE October 11, 1994

SURVEYORS SIGNATURE

Robert C. Sipes

SURVEYORS JOB NO.

94101101



Sec 17

Clear Creek

5/6

M KODMAN
D.R. 415 PG 641
55 AS
CEDAR

COMPANY
D.R. 480 PG 356
30-31
7.20 AS

INSTR. # 2000011481
1.00 AS

1.00 AS

D.R. 211 PG 355
113 AS

BLUFF ROAD RSID000705

N 89° 49' 13" E

BLUFF

CICr_G11

N-E CORNER, S-W 1/4
SECTION 17, T1N, R1W
MONROE CO., IND.

STEVEN & AGATHA AUSTIN
INSTR # 1999 013 641
1.07 AS

1 STORY
FRAME
DWELLING

1 STORY
FRAME
DWELLING

CONC.
BLOCK
GARAGE

ASPHALT

Jim Fielder
Monroe County Recorder IN
IN 2002023740 SURVEY
10/11/2002 10:30:29 1 PGS
Filing Fee: \$9.00

MELVIN & BARBARA
DECKARD
D.R. 170 PG 108-109
1.73 AS

VERLYN BRADLEY
D.R. 480 PG 356
2.03 AS

S 01° 26' 33" E

432.56

TRACT # 2 0.685 AC

N 00° 54' 22" W

301.41

TRACT # 1
2.40 AS

IN. #2002021444

450.79'

S 01° 26' 33" E

SCALE 1"=50'
DAVID HAYS

MELVIN & BARBARA
DECKARD
D.R. 170 PG 108-109
2.08 AS

HOWARD MITCHELL
D.R. 153 PG 64
.05 AS

N 01° 26' 33" W
20'

JEFFREY & LOUANN RAY
D.R. 478 PG 670-671
HARDING PLACE SUBDIVISION
LOT # 2

1/4 SECTION
LINE

RECEIVED

SEP 25 2002


MONROE COUNTY PLANNING
OWNER OF RECORD: David K. & Misti D. Hays

INSTRUMENT # 2002021442 - 2002021444


8301 ANN AVE
BLOOMINGTON, IN. 47401

SURVEYOR'S NOTE:

This Plat and attached descriptions is the result of data of record and
is not the result of a complete field survey.



Lee Utt
Lee Utt, R. L. S. # S0089, Indiana
1604 South Henderson Street
Bloomington, Indiana 47401
September 13, 2002



RECEIVED

SEP 25 2002

MONROE COUNTY PLANNING DEPARTMENT OF RECORD: David K. & Misti D. Hays

INSTRUMENT # 2002021442 - 2002021444

SURVEYOR'S NOTE:

This Plat and attached descriptions is the result of data of record and is not the result of a complete field survey.



Lee Utt, R. L. S. # 50089, Indiana
1604 South Henderson Street
Bloomington, Indiana 47401
September 13, 2002

EXHIBIT "A"

A part of the North one half of the Southwest quarter of Section 17, Township 7 North, Range 1 West, Monroe County, bounded and described as follows: Beginning at the Northeast corner of said Southwest quarter; thence from said point of beginning and with the East line of said Southwest quarter and running South 01 degrees 26 minutes 33 seconds East for 450.79 feet; thence South 89 degrees 28 minutes 54 seconds West for 233.42 feet; thence North 01 degrees 26 minutes 33 seconds West for 20.00 feet; thence North 00 degrees 54 minutes 22 seconds West for 301.41 feet; thence North 01 degrees 26 minutes 33 seconds West for 130.71 feet and to the North line of said Southwest quarter; thence North 89 degrees 49 minutes 13 seconds East for 230.62 feet and to the point of beginning. Containing 2.40 acres, more or less.

Subject to a Twenty-five (25) foot right of way for Cedar Bluff Road.

Also known as *Tract 1* as prepared by: Lee Utt, R.L.S. #S0089 dated September 13, 2002.

A part of the North one half of the Northwest quarter of Section 17, Township 7 North, Range 1 West, Monroe County, Indiana, bounded and described as follows: Beginning at a point on the North line of said Southwest quarter, said point of beginning being South 89 degrees 49 minutes 13 seconds West, 230.62 feet from the Northeast corner of said Southwest quarter; thence from said point of beginning and continuing South 89 degrees 49 minutes 13 seconds West for 70.00 feet; thence leaving said North line and running South 01 degrees 26 minutes 33 seconds East for 432.56 feet; thence North 89 degrees 28 minutes 54 seconds East for 67.17 feet; thence North 00 degrees 54 minutes 22 seconds West for 301.41 feet; thence North 01 degrees 26 minutes 33 seconds West for 130.71 feet and to the point of beginning. Containing 0.685 acre, more or less.

Subject to a Twenty-five (25) foot right of way for Cedar Bluff Road.


Also known as *Tract 2* as prepared by: Lee Utt, R.L.S. #S0089 dated September 13, 2002.



In accordance with the Subdivision Control Ordinance, this parcel was created by Administrative Subdivision, TYPE E on Oct. 11, 2002

Clear Creek 17
TYPE E ADMINISTRATIVE SUBDIVISION

A part of the Southeast quarter of
Section 17, T-7-N, R-1-W,
Monroe County, Indiana



SECTION 17, T-7-N, R-1-W,
MONROE COUNTY, IN.

LEGEND

- CL = CENTERLINE
- (R) = RECORD
- (M) = MEASURED
- (C) = CALCULATED (NOT SET)
- (N/F) = LAND NOW OR FORMERLY OF
- ⊕ = 5/8" REBAR W/CAP ENGRAVED "R.L.S. Bennett S0438" (SET FLUSH)
- ⊗ = 5/8" HUTER REBAR (FOUND FLUSH)
- ⊙ = 5/8" REBAR (FOUND 1" B.G.)
- ⊖ = 5/8" REBAR (FOUND 8" A.G.)
- ⊙ = 5/8" PIPE (FOUND FLUSH)
- = 3"x3" STONE (FOUND)
- △ = RAILROAD SPIKE (FOUND 1" B.G.)
- = 1" PINCH PIPE (FOUND FLUSH)
- = CONCRETE NAIL (FOUND FLUSH)


INST.# = INSTRUMENT NUMBER
D.R. = DEED RECORD BOOK / PAGE
A.G. = RELATIONSHIP ABOVE THE SURFACE OF THE GROUND
B.G. = RELATIONSHIP BELOW THE SURFACE OF THE GROUND

SCALE: 1" = 100'

DRAWN BY: CRT
CHECKED BY: JCB

JOB NUMBER: B200766

NOTES:
1) Basis of bearing based on monuments found on West line of Reference survey #1.
2) Per Community Panel #180169 0020 C, this property is not located in a flood zone.
3) All distances are measured distances unless otherwise noted.




TRICO Surveying Services, Inc.
110 South First Street, Ellettsville, Indiana. 47429
Phone: 812-876-0450 Fax: 812-876-0452

NEAL BOUNDARY SURVEY

Reference is made to a surveyor's report and descriptions of same date to be included herewith.

Surveyor's Signature: James C Bennett
James C. Bennett R.L.S. # S0438 Certification Date: DECEMBER 12, 2007




A PART OF THE SOUTHEAST QUARTER OF
SECTION 17, TOWNSHIP 7 NORTH, RANGE 1 WEST
MONROE COUNTY, INDIANA

NOTES:

- 1) 3/8" Rebar will be set at all property corners.
- 2) Fieldwork completed September 2009.
- 3) Basis of bearing (State Plane).
- 4) Source of title Now or Formerly owned by Steven C. Austin Instrument Number 2002026148 as found in the office of the Monroe County Recorder.
- 5) Reference is made to a survey performed by Lee Utt for Robert Sims dated August 13th, 1975.
- 6) Reference is made to a survey performed by Bledsoe, Tapp & Riggert dated August 6th, 1997.

7) I affirm, under penalty of perjury, that I have taken responsible care to redact each Social Security number in this document, unless required by law.
- ERIC L. DECKARD




LOCATION MAP

LEGEND

- STONE FOUND
- REBAR FOUND
- REBAR SET
- RIGHT-OF-WAY
- RR SPIKE FOUND
- PIPE FOUND
- FENCE
- OVERHEAD POWER LINE
- RECORD
- MEASURED
- MAG SPIKE SET

PROJECT LOCATION
2009018223 SURVEY \$17.00
10/16/2009 11:15:42A 4 PGS
Monroe County Recorder IN
Recorded as Presented



CERTIFICATION


The within survey was performed without benefit of source of title and is subject to any statement of facts revealed by the same.

Easements have been located in the field and prepared with this survey drawing. This qualification will be removed upon receipt and inspection of current title work.

Subject to the above reservation, the survey work shown hereon was performed either by me or under my direct supervision and control and to the best of my knowledge and belief was performed according to the survey requirements in 865 IAC 12-1 through 19.

Certified this 30 day of September 2009

Eric L. Deckard
Registered Surveyor LS29900012
State of Indiana



SCALE 1" = 60'

DAN RAREY		DECKARD LAND SURVEYING 1604 S. HENDERSON ST. BLOOMINGTON IN. 47401 (812)961-0235
BOUNDARY SURVEY	SHEET 1 OF 4	
DRAWN BY: AEW DATED:09/30/09	CHECKED BY: ELD	PROJECT NO.09-124
SCALE 1"=60'		

DECKARD LAND SURVEYING
1604 S. Henderson St.
Bloomington IN. 47401
(812) 961-0235

SURVEY DESCRIPTION
DAN RAREY
JOB NO. 09-124

A part of the Southeast Quarter of Section 17, Township 7 North, Range 1 West, Monroe County, Indiana, being more particularly described as follows:

BEGINNING at railroad spike marking Northwest corner of the Southeast Quarter of said Section 17; thence along the north line of said quarter section North 89 degrees 56 minutes 25 seconds East for a distance of 384.00 feet to a mag spike; thence leaving said north line South 01 degrees 22 minutes 42 seconds East for a distance of 124.00 feet passing through a rebar stamped Deckard at 20.00 feet; thence South 89 degrees 56 minutes 25 seconds West for a distance of 384.00 feet to a rebar stamped Deckard; thence North 01 degrees 22 minutes 42 seconds West for a distance of 124.00 feet to the Point of Beginning passing through a rebar stamped Deckard at 104.00 feet, containing 1.09 acres more or less.


Subject to the right-of-way of Cedar Bluff Road and all easements of record.

The within survey was performed without the benefit of source of title and is subject to any statement of facts revealed by the same.

Subject to the above reservation, the survey work shown hereon was performed either by me or under my direct supervision and control and to the best of my knowledge and belief was performed according the survey requirements in 865 IAC 1-12-1 through 19.

Certified this 30 day of September 2009.


Eric L. Deckard
Registered Land Surveyor LS29900012
State of Indiana



**SURVEYOR'S REPORT
DAN RAREY
JOB NO. 09-124**

In accordance with Title 865. IAC. 1-12 sections 1-30 of the Indiana Administrative Code, the following observations and opinions are submitted regarding the various uncertainties in the location of lines and corners established on this survey as a result of:

- A). (Variances) in the reference monuments
- B). (Discrepancies) in the record description and plats
- C). (Inconsistencies) in lines of occupation and;
- D). (Relative Positional Accuracy) "RPA"

The relative positional accuracy (due to random errors in measurement) of this survey is within that allowable for a Rural survey (0.26' plus 200 PPM) as defined I.A.C. Title 865 ("relative positional accuracy" means the value expressed in feet or meters that represents the uncertainty due to random errors in measurements in the location of any point on a survey relative to any other point on the same survey at the 95 percent confidence level.")

SUBJECT PROPERTY:

A boundary survey was performed on the property now or formerly owned by Steven C. Austin as found in Instrument Number 2002026148 in the office of the Monroe County Recorder. This Property is located in Section 17, Township 7 North, Range 1 West, Monroe County, Indiana. The purpose of this survey is to retrace the boundary lines of the subject property.

REFERENCE MONUMENTS:

- A). A railroad spike was found 0.20 feet below grade marking the Northwest corner of the Southeast quarter of Section 17, Township 7 North, Range 1 West, Monroe County, Indiana. This monument is of record in the Monroe County Surveyor's office as Corner I.D. Clear Creek G-11. The spike was witnessed by Steven V. Farkas on March 7th, 2002 and was accepted and held as said corner. This monument was also found to be referenced in a survey for performed by Bledsoe, Tapp & Riggert dated August 6th, 1997.
- B). A broken concrete right-of-way monument was found 1.2 feet below grade 50 feet east of the centerline of Old State Road 37 marking a point on the north line of the Southeast quarter of Section 17, Township 7 North, Range 1 West. This monument was found to be referenced in a survey performed by Lee Utt for Robert Sims dated August 13th, 1975. This monument was accepted and held to perpetuate the North line of said Section 17.
- C). A rebar stamped "Bennett - LS# 80040438" was found 0.40 feet above grade marking a point on the west line of the Southeast quarter of Section 17, Township 7 North, Range 1 West, Monroe County, Indiana. This monument was accepted and held to perpetuate the West line of said quarter section.

LINES OF OCCUPATION:

The lines of occupation, which affect this survey, are detailed as follows:

- 1). The centerline of Cedar Bluff Road was found running east and west along the entire north line of the subject property. The centerline meanders from 0.0 feet north of line at the west end to 2.5 feet south of line at the east end.

DECKARD LAND SURVEYING, LLC
1604 S. Henderson St.
Bloomington IN. 47401
(812) 961-0235

- 2). A wood privacy fence was found running in the north and south direction along the entire east line of the subject property. This fence meanders from 4.4 feet east of line at the north end to 4.8 feet west of line at the south end.
- 3). A metal barn was found 1.10 feet west line at the Southeast corner of the subject property.
- 4). A wood rail fence was found running east and west along the entire south line of the subject property. This fence meanders from 0.5 feet north of line at the east end to 0.2 feet south of line at the west end.
- 5). No lines of occupation were found along the west line of the subject property.

RECORD DESCRIPTIONS:


- 1). No discrepancies were found in the record descriptions.

The within survey was performed without benefit of source of title and is subject to any statement of facts revealed by the same.

Subject to the above reservation, the survey work shown hereon was performed either by me or under my direct supervision and control and to the best of my knowledge and belief was performed according to the survey requirements in 865 IAC 1-12-1 through 19.

Certified this 30 day of September, 2009


ERIC L. DECKARD
Registered Land Surveyor No. 29900012
State of Indiana



A PART OF THE SOUTHEAST QUARTER OF
SECTION 17, TOWNSHIP 7 NORTH, RANGE 1 WEST
MONROE COUNTY, INDIANA

NOTES:

1) $\frac{1}{4}$ " Rebar will be set at all property corners.

2) Fieldwork completed September 2009.

3) Basis of bearing (State Plane).

4) Source of title Now or Formerly owned by
Steven C. Austin Instrument Number
2002026148 as found in the office of the
Monroe County Recorder.

5) Reference is made to a survey performed by
Lee Utt for Robert Sims dated August 13th,
1975.

6) Reference is made to a survey performed by
Bledsoe, Tapp & Riggert dated August 6th,
1997.

7) I affirm, under penalty of perjury, that I
have taken responsible care to redact each
Social Security number in this document, unless
required by law.
- ERIC L. DECKARD


LEGEND

- STONE FOUND
- ⊙ REBAR FOUND
- ⊙ REBAR SET
- ◇ RIGHT-OF-WAY
- ⊗ RR SPIKE FOUND
- PIPE FOUND
- x—x— FENCE
- ||—||— OVERHEAD POWER LINE
- (R) RECORD
- (M) MEASURED
- △ MAG SPIKE SET



LOCATION MAP

PROJECT LOCATION



CERTIFICATION



The within survey was performed without benefit of source of title and is subject to any statement of facts revealed by the same.

Easements have been located in the field and prepared with this survey drawing. This qualification will be removed upon receipt and inspection of current title work.

Subject to the above reservation, the survey work shown hereon was performed either by me or under my direct supervision and control and to the best of my knowledge and belief was performed according to the survey requirements in 865 IAC 1-12-1 through 19.

Certified this 30 day of September, 2009

Eric L. Deckard
Registered Surveyor LS29900012
State of Indiana



SCALE 1" = 60'

DAN RAREY			PLANNING SURVEYING MAPPING	DECKARD LAND SURVEYING 1604 S. HENDERSON ST. BLOOMINGTON IN. 47401 (812)961-0235
BOUNDARY SURVEY		SHEET 1 OF 4		
DRAWN BY: AEW DATED:09/30/09	CHECKED BY: ELD	SCALE 1"=60'	PROJECT NO.09-124	

SEC 17

CC

DECKARD LAND SURVEYING
1604 S. Henderson St.
Bloomington IN. 47401
(812) 961-0235

SURVEY DESCRIPTION
DAN RAREY
JOB NO. 09-124

A part of the Southeast Quarter of Section 17, Township 7 North, Range 1 West, Monroe County, Indiana, being more particularly described as follows:

BEGINNING at railroad spike marking Northwest corner of the Southeast Quarter of said Section 17; thence along the north line of said quarter section North 89 degrees 56 minutes 25 seconds East for a distance of 384.00 feet to a mag spike; thence leaving said north line South 01 degrees 22 minutes 42 seconds East for a distance of 124.00 feet passing through a rebar stamped Deckard at 20.00 feet; thence South 89 degrees 56 minutes 25 seconds West for a distance of 384.00 feet to a rebar stamped Deckard; thence North 01 degrees 22 minutes 42 seconds West for a distance of 124.00 feet to the Point of Beginning passing through a rebar stamped Deckard at 104.00 feet, containing 1.09 acres more or less.

Subject to the right-of-way of Cedar Bluff Road and all easements of record.


The within survey was performed without the benefit of source of title and is subject to any statement of facts revealed by the same.

Subject to the above reservation, the survey work shown hereon was performed either by me or under my direct supervision and control and to the best of my knowledge and belief was performed according the survey requirements in 865 IAC 1-12-1 through 19.

Certified this 30 day of September, 2009.



Eric L. Deckard
Registered Land Surveyor LS29900012
State of Indiana



DECKARD LAND SURVEYING, LLC
1604 S. Henderson St.
Bloomington IN. 47401
(812) 961-0235

SURVEYOR'S REPORT
DAN RAREY
JOB NO. 09-124

In accordance with Title 865, IAC. 1-12 sections 1-30 of the Indiana Administrative Code, the following observations and opinions are submitted regarding the various uncertainties in the location of lines and corners established on this survey as a result of:

- A). (Variances) in the reference monuments
- B). (Discrepancies) in the record description and plats
- C). (Inconsistencies) in lines of occupation and;
- D). (Relative Positional Accuracy) "RPA"

The relative positional accuracy (due to random errors in measurement) of this survey is within that allowable for a Rural survey (0.26' plus 200 PPM) as defined I.A.C. Title 865 ("relative positional accuracy" means the value expressed in feet or meters that represents the uncertainty due to random errors in measurements in the location of any point on a survey relative to any other point on the same survey at the 95 percent confidence level.")

SUBJECT PROPERTY:

A boundary survey was performed on the property now or formerly owned by Steven C. Austin as found in Instrument Number 2002026148 in the office of the Monroe County Recorder. This Property is located in Section 17, Township 7 North, Range 1 West, Monroe County, Indiana. The purpose of this survey is to retrace the boundary lines of the subject property.

REFERENCE MONUMENTS:

- A). A railroad spike was found 0.20 feet below grade marking the Northwest corner of the Southeast quarter of Section 17, Township 7 North, Range 1 West, Monroe County, Indiana. This monument is of record in the Monroe County Surveyor's office as Corner I.D. Clear Creek G-11. The spike was witnessed by Steven V. Farkas on March 7th, 2002 and was accepted and held as said corner. This monument was also found to be referenced in a survey for performed by Bledsoe, Tapp & Riggert dated August 6th, 1997.
- B). A broken concrete right-of-way monument was found 1.2 feet below grade 50 feet east of the centerline of Old State Road 37 marking a point on the north line of the Southeast quarter of Section 17, Township 7 North, Range 1 West. This monument was found to be referenced in a survey performed by Lee Utt for Robert Sims dated August 13th, 1975. This monument was accepted and held to perpetuate the North line of said Section 17.
- C). A rebar stamped "Bennett - LS# 80040438" was found 0.40 feet above grade marking a point on the west line of the Southeast quarter of Section 17, Township 7 North, Range 1 West, Monroe County, Indiana. This monument was accepted and held to perpetuate the West line of said quarter section.

LINES OF OCCUPATION:

The lines of occupation, which affect this survey, are detailed as follows:

- 1). The centerline of Cedar Bluff Road was found running east and west along the entire north line of the subject property. The centerline meanders from 0.0 feet north of line at the west end to 2.5 feet south of line at the east end.

DECKARD LAND SURVEYING, LLC
1604 S. Henderson St.
Bloomington IN. 47401
(812) 961-0235

- 2). A wood privacy fence was found running in the north and south direction along the entire east line of the subject property. This fence meanders from 4.4 feet east of line at the north end to 4.8 feet west of line at the south end.
- 3). A metal barn was found 1.10 feet west line at the Southeast corner of the subject property.
- 4). A wood rail fence was found running east and west along the entire south line of the subject property. This fence meanders from 0.5 feet north of line at the east end to 0.2 feet south of line at the west end.
- 5). No lines of occupation were found along the west line of the subject property.

RECORD DESCRIPTIONS:

- 1). No discrepancies were found in the record descriptions.

The within survey was performed without benefit of source of title and is subject to any statement of facts revealed by the same.

Subject to the above reservation, the survey work shown hereon was performed either by me or under my direct supervision and control and to the best of my knowledge and belief was performed according to the survey requirements in 865 IAC 1-12-1 through 19.


Certified this 30 day of September, 2009


ERIC L. DECKARD
Registered Land Surveyor No. 29900012
State of Indiana



17-7-1W & 20-7-1W
PART SE 1/4 SECTION 17
T 7N, R 1W
Monroe County, Indiana


○ = 5/8" REBAR W/ CAP SET



SURVEYOR'S SIGNATURE

Raymond Graham
RAYMOND GRAHAM
R.P.E. 8409 R.L.S. 8978
815 WEST KIRKWOOD AVENUE
BLOOMINGTON, IN 47404
DECEMBER 3, 1999 JOB NO. 99-577

OLD STATE ROAD #37



EAST 104.00'

N04°45'00"E 758.52'

S89°52'33"E 901.54'

35.43 ACRES

(18.40 ACRES - SECT. 17)

SECTION 17

SECTION 20

(17.03 ACRES - SECT. 20)

WEST 1629.87'

REBAR FOUND

S30°06'33"E 199.89'

S10°01'38"E 590.25'

STATE ROAD

WOOD FENCE POST FD

WEST

133.36' C1Cr_I13


SE CORNER
SE 1/4
SECTION 17
T 7N, R 1W

S02°10'17"W 530.38'

NUMBER 37

R/W

PART SE 1/4 SECTION 17, T 7N, R 1W
Monroe County, Indiana



DESCRIPTION:

A PART OF THE SOUTHEAST QUARTER OF SECTION 17, TOWNSHIP 7 NORTH, RANGE 1 WEST, MONROE COUNTY, INDIANA, DESCRIBED AS FOLLOWS: COMMENCING AT THE SOUTHEAST CORNER OF THE SAID QUARTER SECTION; THENCE WEST ALONG THE SOUTH LINE OF THE SAID SECTION 17 FOR 133.38 FEET AND TO THE POINT OF BEGINNING; THENCE CONTINUING ALONG THE SAID SOUTH LINE WEST FOR 1167.29 FEET; THENCE LEAVING THE SAID SOUTH LINE NORTH 04 DEGREES 45 MINUTES 00 SECONDS EAST FOR 758.52 FEET; THENCE SOUTH 89 DEGREES 52 MINUTES 33 SECONDS EAST FOR 901.54 FEET AND TO THE WESTERLY RIGHT-OF-WAY OF STATE ROAD NUMBER 37; THENCE WITH THE SAID RIGHT-OF-WAY SOUTH 30 DEGREES 06 MINUTES 33 SECONDS EAST FOR 199.69 FEET; THENCE SOUTH 10 DEGREES 01 MINUTES 38 SECONDS EAST FOR 590.23 FEET AND TO THE POINT OF BEGINNING. CONTAINING 18.40 ACRES, MORE OR LESS.

○ = 5/8" REBAR W/ CAP SET


SURVEYOR'S SIGNATURE

Raymond Graham

RAYMOND GRAHAM
R.P.E. 8409 R.L.S. 9978
815 WEST KIRKWOOD AVENUE
BLOOMINGTON, IN 47404
DECEMBER 3, 1999 JOB NO. 99-577

SCALE
0 200
FEET

PART SE 1/4 SECTION 17
T 7N, R 1W
Monroe County, Indiana



DESCRIPTION:
A PART OF THE SOUTHEAST QUARTER OF SECTION 17, TOWNSHIP 7 NORTH, RANGE 1 WEST, MONROE COUNTY, INDIANA DESCRIBED AS FOLLOWS: COMMENCING AT THE SOUTHEAST CORNER OF THE SAID QUARTER SECTION; THENCE WEST ALONG THE SOUTH LINE OF SAID SECTION FOR 133.36 FEET AND TO THE WESTERLY RIGHT-OF-WAY OF STATE ROAD NUMBER 37; THENCE LEAVING THE SAID SOUTH SECTION LINE AND ALONG THE SAID RIGHT-OF-WAY NORTH 10 DEGREES 01 MINUTE 38 SECONDS WEST 590.23 FEET; THENCE NORTH 30 DEGREES 06 MINUTES 33 SECONDS WEST FOR 199.69 FEET; THENCE LEAVING THE SAID RIGHT-OF-WAY NORTH 89 DEGREES 52 MINUTES 33 SECONDS WEST FOR 901.54 FEET AND TO THE POINT OF BEGINNING; THENCE SOUTH 04 DEGREES 45 MINUTES 00 SECONDS WEST FOR 296.52 FEET; THENCE WEST FOR 104.00 FEET; THENCE NORTH 03 DEGREES 43 MINUTES 17 SECONDS EAST FOR 197.98 FEET; THENCE WEST FOR 330.00 FEET AND TO THE CENTERLINE OF OLD STATE ROAD 37; THENCE WITH THE SAID ROAD CENTERLINE NORTH 02 DEGREES 34 MINUTES 29 SECONDS EAST FOR 98.99 FEET; THENCE LEAVING THE SAID ROAD CENTERLINE SOUTH 89 DEGREES 52 MINUTES 33 SECONDS EAST FOR 441.26 FEET AND TO THE POINT OF BEGINNING. CONTAINING IN ALL 1.47 ACRES, MORE OR LESS.

R/W 50'

SURVEYOR'S SIGNATURE Raymond Graham
RAYMOND GRAHAM
R.P.E. 8409 R.L.S. 9978
615 WEST KIRKWOOD AVENUE
BLOOMINGTON, IN 47404
DECEMBER 3, 1999 JOB NO. 99-577